

## Village of Gulfport Henderson Pump Station Package No.1

- **Bid Date:** February 3, 2017 at 1:00 PM at Klingner & Associates, P.C., 610 N 4th Street, Suite 100, Burlington, Iowa
- **Pre-Bid:** January 11, 2017 at 1:30 PM at Klingner & Associates, P.C., 610 N 4th Street, Suite 100, Burlington, Iowa
- **Plans Available:** December 30, 2016 from City Blue Technologies, Rock Island, IL 61201, phone: 309-277-3000.
- **Bid Range:** \$2.5-3.5 Million
- **Location:** Village of Gulfport, Illinois

**Contract Documents:** including drawings and Specification Manual are on file and may be viewed at the office of Klingner & Associates, P.C., 610 North 4th Street, Suite 100, Burlington, Iowa 52601 and obtained from City Blue Technologies, Rock Island, Illinois 61201, <http://www.citybluetechnologies.com>.

**Scope:** Work consists of partial structural demolition of the 1913 Pump Station including ancillary asbestos abatement; the construction of a sheet pile retaining wall and pump basin and ancillary structural steel superstructure to install two (2) owner supplied electric 42 inch 40,000 GPM drainage pumps and to connect to the existing nominal 48 inch discharge pipes remaining in the 1913 Pump Station. Work also includes the construction of an elevated concrete platform supporting a pre-engineered steel building containing miscellaneous electrical, mechanical, plumbing and operational systems and controls associated with the new pumps as well as selective mechanical dredging and placement of riprap and submerged articulated concrete block revetment and geotextile fabric.

- **Project Manager:** Bryan Bross, PE RG, 319-752-3603