

County of Adams, Illinois
NEW QUINCY AMBULANCE FACILITY

- **Bid Date:** Monday, January 9th, 2016 at 2:00 PM
- **Pre-Bid:** Wednesday, December 28, 2016 at 2:00 PM (Voluntary)
- **Location:** Adams County Health Dept., 330 Vermont St., Quincy, IL 62301
- **Contract Documents:** including Drawing and Technical Specifications, are on file and may be viewed at the office of Klingner & Associates, P.C., 616 N 24th Street, Quincy, Illinois 62301 and obtained electronically at no cost from CityBlue Technologies, Peoria, IL 62301, <http://www.citybluetechologies.com/>
- **Scope:** Base Bid: Construct New 6,463 SF Quincy Ambulance Facility consisting of approximately 3,400 SF of living quarters and 3,000 SF apparatus garage. Building shall be “essential facility rated” pre-engineered steel building with 16’ eave height and 2:12 sloped galvalume metal roof panels. West end of building shall have an expansion main frame to allow for future bays. Panelized stone veneer shall be installed to the window sills on the north and east walls. Face-applied horizontal ribbed metal accent panels shall be installed from 12’ AFF to bottom of eave on north and same width continues on east façade. Tensile rod canopies shall be installed over north and east entrance doors. An approximately 250 SF mechanical mezzanine shall be constructed on top of an interior pre-cast concrete storm shelter room. Mezzanine shall be accessed by an alternating tread stair from apparatus garage. Living quarters shall be predominantly stained concrete floors, gypsum board walls painted and SAT or suspended gypsum board ceilings. Training room and office will receive carpet tile and entry vestibule will receive walk-off carpet tile. Full height 2-hour fire rated walls will separate the apparatus garage from the living quarters and separate the sleeping rooms (required limited fire sprinkler system) from the rest of the living quarters.
- **Project Manager:** Debbie E. Naught, A.I.A., 217.223.3670